

तातडीचे

e-mail: cgeuno3@gmail.com

जा.क्र.मुद्दाउविप-३/पेठ वसाहत/तांत्रिक शाखा-१/१९५४/सन २०२२

कार्यकारी अभियंता,
मुख्य द्वार उभारणी विभागीय पथक क्र.३,
पेठ वसाहत-इस्लामपूर यांचे कार्यालय
दिनांक- २५.११.२०२२

प्रति,

मा.अधीक्षक अभियंता,
यांत्रिकी मंडळ, कोल्हापूर

विषय - जेसीबी जेएस-८१ एक्स्केव्हेटरच्या दोन्ही बाजूच्या ट्रॅक चेनच्या ग्राऊजर शू वर रबर पॅड बसविणेसाठीची दरपत्रके मागविणेसाठीची बजेटरी ऑफर प्रसिध्दीस देणेबाबत

उपरोक्त विषयास अनुसरून सविनय सादर करण्यात येते की, या विभागांतर्गत उपविभागाकडील संयंत्राद्वारे सांगली पाटबंधारे मंडळाकडील विविध प्रकल्पाच्या मातीकाम व कालवा स्वच्छतेची कामे केली जातात. या मंडळांतर्गत असलेल्या कालवा वितरण व्यवस्थेमध्ये बहुतांशी कालवे हे काँक्रीट लाईन्ड आहेत. अशा कालव्याची स्वच्छता करून देणेची संबंधीत स्थापत्य विभागाची मागणी आहे.

सध्या असलेल्या पारंपारिक एक्स्केव्हेटरच्या वापरामुळे काँक्रीट लाईनिंग तुटत असल्याने पर्यायी अनुरूप संयंत्राची त्यांचेकडून मागणी होत असते. अशा परिस्थितीत या विभागाकडील उपलब्ध ८ टन क्षमतेच्या जेसीबी जेएस-८१ एक्स्केव्हेटरला दोन्ही बाजूच्या ट्रॅक चेनच्या ग्राऊजर शू वर रबर पॅड बसविणे प्रस्तावित आहे. या कामासाठीची दरपत्रके मागविणेसाठीची बजेटरी ऑफर नोटीस मंडळ कार्यालयामार्फत प्रसिध्दीस देणेसाठी सोबत सादर करणेत येत आहे. तरी सोबत जोडलेल्या अनुसूचीप्रमाणे बजेटरी ऑफर नोटीस प्रसिध्दीस देण्यात यावी, ही विनंती.

सोबत- बजेटरी ऑफर नोटीस

(आ.ना.मोरे)

कार्यकारी अभियंता
मुख्य द्वार उभारणी विभागीय पथक क्र.३
पेठ वसाहत-इस्लामपूर

प्रत- उप अभियंता, मुख्य द्वार उभारणी विभागीय उप पथक क्र.३क, पेठ वसाहत-इस्लामपूर यांना माहितीसाठी रवाना.

Government of Maharashtra
Water Resources Department
Superintending Engineer, Mechanical Circle, Kolhapur

Budgetary offer for the following work (*Non DSR items*) are invited by the Executive Engineer, Chief Gate Erection Divisional Unit No.3, Peth Vasahat - Islampur on behalf of Governor of Maharashtra for estimation purpose from the reputed Manufacturers/Suppliers/Job Workers.

The Government of Maharashtra, Water Resources Department, has undertaken the various works of Dam Earthwork and Canal cleaning, repairs, River/Stream regradation works by using heavy earth moving machinery. In context to this, it is proposed to install Bolt-on Rubber pad to fit to the track shoes on Track chain of **JCB JS-81 Excavator (8 Ton)** having 450 mm wide Triple Grouser Shoes 39 Nos. on each side track chain, which makes it suitable for bed cleaning of concrete lined canal. The details and short specifications of work is available on the website mentioned below.

It is requested to send the budgetary offer mentioning complete rate with rate analysis for the same. The rates will cover all taxes and duties applicable. The offer should reach this office on or before **11.12.2022**. Further it is requested to forward relevant Technical literature, brochures of equipment's attachment/accessories and your comments if any.

Sr. No.	Name of work	Remarks
1	Providing and installing Bolt-on Rubber pad to fit to the track shoes on Track chain of JCB JS-81 Excavator (8 Ton) having 450 mm wide Triple Grouser Shoes 39 Nos. on each side track chain	Please refer Website for detailed Schedule
<u>Note:</u> Please quote your rates for each item separately inclusive of material, machinery and labour and transportation charges etc. mentioning GST separately		

This information is required for the purpose of framing of working estimates and hence the urgency. This Budgetary offer is also available on website www.mahayantriki.org Bidder is requested to act in given time frame.

No. CGEU-3/TS-1/Rubber pad/**1954**/of 2022
Office of the Executive Engineer,
Chief Gate Erection Divisional Unit No.3,
Peth Vasahat-Islampur PIN- 415409
e-mail: cgeuno3@gmail.com
Date: 25.11.2022

(A.N.More)
Executive Engineer
Chief Gate Erection Divisional Unit No.3
Peth Vasahat-Islampur

Copy submitted to the Superintending Engineer, Mechanical Circle, Kolhapur for favor of information please.
Enclosure: Schedule

Copy forwarded to Deputy Engineer, Chief Gate Erection Divisional Sub Unit No.3C, Peth Vasahat-Islampur
Enclosure: Schedule

Copy to M/s.-

1. Siddharth Auto Engineers Pvt. Ltd., Authorised Dealer of JCB, NH-4, Karad – 415110
2. Total Earthmovers Pvt. Ltd., Manas Prayag, Palaspa Phata, Kolke Village, Mumbai Goa Bypass Road, Raigarh – 410221
3. Om Hydraulics Equipments, MH-4, Vishwakarma Nagar, M.K.Sutar Garrage, Ujalaiwadi, Kolhapur – 416004 customer.care@omhydraulics.co.in
4. Eclat Engineers,
84/2, Manas Bunglow, Sinhgad Colony, Jawalkarnagar, Pimpale Gurav, Pune, M.S.411061
5. Modern Distributing Co., 464, SVP Road, Laxmi Buwan, First Floor, C Wing, Opp Marwadi Vidyalaya, Mumbai-400 004
e-mail: modern.mdc@gmail.com
6. Track & Trackto, 12, Vijay Chambers, Ground floor, Tribuvan road, Opp Dream;and Cinema, Mumbai – 400 004
e-mail: Sanjay.jogani@gmail.com
7. Shah Trade Corporation, 16, Majestic Shopping Center, 144, Girgaun road, Mumbai-400004
e-mail: shahtrade_79@yahoo.co.in
8. Raviraj Engineering and Fabrimech, MIDC Kupwad, Sangli
9. Safe Engineers and Fabricators, 42K, MIDC, Satara - 415003

SCHEDULE

Providing and installing Bolt-on Rubber pad to fit to the track shoes on Track chain of JCB JS-81 Excavator

<i>Sr. No.</i>	<i>Description</i>	<i>Qty.</i>	<i>Unit</i>	<i>Rate (Rs.)</i>	<i>Amount (Rs.)</i>
1	Providing and installing Bolt-on Rubber pad to fit to the track shoes on Track chain of JCB JS-81 Excavator (8 Ton) having 450 mm wide Triple Grouser Shoes 39 Nos. on each side track chain:				
	a) Removing all existing 39 No. grouser shoes of both side chains and Drilling additional holes 4 Nos. each for bolt size M14 on the grouser shoe to fit the Bolt-on rubber pad. Refitting after drilling holes.	1	Job		
	b) Providing and installing Bolt-on Rubber pad on grouser shoes 39 Nos. each on both side chains along with Nut-Bolt and washers with specified torque of 178 Nm. <ul style="list-style-type: none"> • Pad width – 450 mm • Style – Bolt on • Core bar – 4 mm steel • Rubber compound – Heavy duty natural and synthetic fibre virgin rubber. • Pad life – 3 to 5 years • Warranty – 12 Months <p>-Bolt-on Rubber pad should be designed for high traction, high durability, anti-chunking, anti-cut and good turn ability.</p> <p>-Each rubber track pad is secured by low heat generation, which can prevent your rubber pad from aging and extend its service life.</p> <p>-They are all properly vulcanized to meet high standards.</p> <p>-Tread pattern designed for improved traction, so as to reduce surface damage and negative impact to the Environment.</p> <p>-They should be provided with pressure relief holes.</p>	1	Job		
	c) Providing and supplying Bolt-on Rubber pad 4 Nos. as per above specifications, additional as a spare for emergency	1	Job		
	d) Material transportation charges	1	Job		
Total Rs.					
Add GST @ ... %					
Gross Total Rs.					

Conditions:

1. The attachment/accessories provided should have specifications as per tender schedule.
2. The 90% payment will be released after minimum 20 Hrs. of trial after fitment of attachment/accessories on machine. Balanced 10% will be released after 6 months or 100 Hrs. of machine usage whichever is earlier.
3. The necessary training regarding installation and removal is to be provided to concerned staff.

(A.N.More)
Executive Engineer
Chief Gate Erection Divisional Unit No.3
Peth Vasahat-Islampur