



**Abstract**


Fabrication and erection of sliding type temporary gate leaf 1.55x1.35m (03 Nos) on river bandhara by way of dismantling old gates. Complete job with material, labour & transportation charges. @..at AmbeBahula river Bandhara on Waldevi River. Tal-Nashik, Dist. Nashik					
Item No.	Description	Qty	Unit	Rate	Amount Rs.
Item No.1	Fabrication & Erection of temporary A frame in std section ISMB100x50, ISA & foundation plates for dismantling of gate leaf for necessary repairs on site, Inspection & Cleaning of gate slot, etc by availing services of labours with necessary materials & equipments complete.	1	Nos of jobs	23467.16	23467.16
Item No.2	Labours charges for a team of Fitter, Welder, Mechanic, Electrician & helpers for Dismantling of corroded blocked gate leaf, from slot & Cleaning and completely for dummy gates for complete job	12	man days	4638.69	55664.28
Item No.3	Sundry Material for Dismantling of gate leaf removing and cleaning for repairs with refitting dummy gates with material, nut bolts. etc complete.	1	Nos of jobs	18262.11	18262.11
Item No.4	Fabrication and erection of sliding type gate leaf of size 1.5x1.3m for water passage insertion in slot on river bandhara	3	Nos of jobs	51729.85	155189.55
Item No.5	Transportation charges for materials, Labours and equipments on site by 6 MT truck from nearest district place Nashik to Ambe Bahula, Bandhara on Waldevi River	250	km	46.62	11655.00
				<b>Rs</b>	<b>264238.00</b>
	Add 1% Insurance			1%	2642.00
	Add 6% CGST			6%	15854.00
	Add 6% SGST			6%	15854.00
	<b>Total cost of work</b>			<b>Rs.</b>	<b>298588.00</b>

  
Section Engineer  
Gate Erection Subdivision Nashik

  
Deputy Engineer  
Gate Erection Subdivision Nashik

**R. No. / 12 / TS -1 of 2021-22**

**Technically sanctioned for Rs. 2,98,588/-**  
Rs (Two lakh Ninty eight thousand five hundred eighty eight only)

  
Engineer  
Gate Erection Unit No. 6  
Nashik - 4

2021-12-14 15:06