

जा.क्र. / २१६५ / यांउसिविक्र.२ / चंद्र / तांशा-१ / धा.क्र.४४/ २०१८	कार्यकारी अभियंता यांत्रिकी उपसा सिंचन विभागक्र.२, बाबुपेठ, चंद्रपुर - ४४२४०३ यांचे कार्यालय
☎ :- (०७१७२)२२७३८२	
फॅक्स :- (०७१७२)२२७३८२	
ई मेल :- mlidn2@rediffmail.com	दि. २८ / १२ / २०१८.

प्रति,

मा. अधिक्षक अभियंता,
यांत्रिकी मंडळ ,
नागपुर

विषय :- वाघोली बुटी, उ.सिं.यो, ता.सावली, जि.चंद्रपुर येथील 2 MVA, 33/6.9 KV Transformer (Mahati Electric Make) च्या दुरुस्ती कामाकरीताचे दर उपलब्ध करुन देणेबाबत.

संदर्भ — उपअभियंता, उ.सिं.यां.व वि. उप. वि. क्र.०२, चंद्रपुर यांचे कार्यालयीन पत्र क्र.१९९, दि.२४/१२/२०१८.

-----0000-----

महोदय,

उपरोक्त संदर्भित पत्रान्वये वाघोली बुटी, उ.सिं.यो, ता.सावली, जि.चंद्रपुर येथील 2 MVA, 33/6.9 KV Transformer (Mahati Electric Make) च्या दुरुस्तीचे दर हे सी.एस.आर. मध्ये व या विभागाकडे उपलब्ध नसल्याने सदर कामाची बजेटरी ऑफर क्र. १०/२०१८-१९, यांत्रिकी संघटनेच्या संकेतस्थळावर (www.mahayantriki.gov.in) प्रसिध्द करण्यात यावी व दर उपलब्ध करुन देण्यात यावे हि विनंती.

कार्यालय	कार्यकारी अभियंता, यांत्रिकी उपसा सिंचन विभाग क्र.२, चंद्रपुर
बजेटरी ऑफर प्रसिध्द करण्याची अंतिम तारीख	दि.०२/०१/२०१९
बजेटरी ऑफर स्विकारण्याची अंतिम तारीख	दि. ११/०१/२०१९

सबब आपले माहीती व पुढील योग्य कार्यवाहीस सविनय सादर.

सहपत्र :- १. बजेटरी ऑफर क्र. १०/२०१८-१९ — १ प्रत

२.Detailed Technical Specification — १ प्रत

(वि.ल.वराडे)
कार्यकारी अभियंता
यांत्रिकी उपसा सिंचन विभाग क्र. २
चंद्रपुर

Budgetory Offer No.10/2018-19

Detailed Technical Specification for Budgetory Offer
Wgholi buti LIS Tah. Saoli .Chandrapur.

Name of Work: Repairs and maintenance of 2 MVA, 33/6.6 KV Transformer (Mahati Electric Make) at Wagholi Buti LIS, Tah.Saoli, Dist.Chandrapur

Sr.No.	Description of Item/Work	Qty.	Rate Rs. /job (Without GST)	Amount (Rs.)
1.	Cost of primary winding new copper strip	1200 Kg		
2.	Cost of Secondary Winding new copper strip	950 Kg		
3.	Rewinding of HV winding with new copper strip	820 Kg		
4.	Labour charges of Dismantling Complete transformer	Lump sum		
5.	Labour charges cleaning of healthy parts including coils, lamination, conservator tank radiator etc.	Lump sum		
6.	Labour charges core coil assembly Re-tanking of transformer, changing of all gasket and minor parts & testing as per IS 2026	Lump sum		
7.	Labour charges of paper Striping from old conductor	Lump sum		
8.	Labour charges for cleaning annealing and reinsulation with new Electrical grade Kraft paper	Lump sum		
9.	Supply of new insulating material spacers, ducts barrier etc.	150 Kg		
10.	Oven Drying of Transformer	Lump sum		
11.	Complete spray painting	1 Job		
12.	Regeneration of Transformer oil to make it new like and bringing acidity level below 0.05 mg KOH/gm.	2000 Ltr.		
13.	Supply of EHV Grade new transformer oil to make up for loss in Regeneration (5%) and Repair (10%)	1000 Ltr.		
14.	Breather	1 No		
15.	Complete Transformer Lifting from site by crane loading Transformer, to & fro vice versa at WagholiButi LIS	1 Job		
16.	Providing new Bushing Kit	1 Job		

-Sd-

(V.L.Warade)

Executive Engineer

Mechanical Lift Irrigation Division No.2

Babupeth,Chandrapur