

①


Abstract


ame of work - Painting of structure, grill work, Power transformer, chain link fencing of 33/6.6 kv switchyard at Wagholi-Buti Lift Irrigation Scheme, Dist. Gadchiroli.

Description of Item	Qty.	Unit	Rate	Amount
Item No.1: Scrapping existing paint of feeder pillar / switchgears and frame of panel board completely without damaging and painting the same with single coat of Red oxide & two coats of approved quality enamel paint in an approved manner. (The square meter area of angle iron frame on which the switchgears are erected shall be considered for measurement purpose) Rate taken from PWD CSR 2019-20 Item no.16-4-11 Page No.245	925	Sqmtr	251.29	232443.25
Item no 2 :- Painting fencing of transformer sub station including all supports, iron work and doors from both sides with one coat of red oxide & two coats of aluminium paint, in an approved manner as per direction. Rate taken from PWD CSR 2019-20 Item no.16-4-10 Page No.245	600	Sqmtr	111.76	67056.00
Total, Rs				299499.25
12% Add GST @ (18%)				353409.86
Rs. 335439.16 Total Amount Rs.				353409.11
Rs. 335439.16 Say, Rs				353409.00


Amount - Three Lac Fifty Three Thousands Four Hundred & Nine Only.

Three lac thirty five thousand four hundred & thirty nine only
estimate prepared by,


B.V. Thakare
Mechanical Engineer


Shri.B.V. Thakare
Deputy Engineer
Lift Irrigation Mechanical & Electrical
Sub-Division No.2 Chandrapur

Sanctioned Estimate No. 01 Year 2020-21 Dt. 11/01/2020
Amount Rs. 335439.16 In Words. Three lacs thirty
five thousand four hundred & thirty nine only.


Executive Engineer
Mechanical Lift Irrigation Dn. No 2
Chandrapur