

# ABSTRACT

Name of work: General Repairs to Tata Tipper MH 20 CU No. 201

Sr. No.	Description	Quantity	Rate	Amount
1	2			3
A	General Repair of Tata Tipper No. MH 20 CU 201 with cost of Labour charges as below :			
	complete job with			
1	Cost of Labour charges	1 Job	27229 30613	27229 30613.00
			Total	27229 30613.00
			CGST 9 %	2451.51 2755.17
			SGST 9 %	2451.51 2755.17
			Total	32142.02 36123.34
			Grand Total	32142/- 36123


(In words :- Thirty six thousand one hundred and twenty three only.)

## CERTIFICATE


certified that,

- 1) Repairs are essential to keep the machine in good working condition.
- 2) Such type of repairs are not done in departmental workshop due to lack of facilities.
- 3) Spares are not available in departmental store
- 4) Rates are reasonable.

  
R.S. Warpe  
(Section Engineer)

  
Deputy Engineer  
Mechanical Subdivision No.2  
Osmanabad.

Sanctioned Estimate No. 212 the year 2021-22  
Estimate technically Sanctioned for Rs. 32142/-  
Rs in Word. Thirty Two Thousand one hundred forty Two.


  
Executive Engineer  
Mechanical Division  
Osmanabad


# Measurement

General Repairs to Tata Tipper MII 20 CU No. 201

Part NO. & Description	Qty	unit	Rate	Amount
2	3	4	5	8
General Repair of Tata Tipper No. MII 20 CU 201 with cost of Labour charges as below :				
Complete fuel line opening, cleaning, checking, brazing and refitting (E/41)	1	Job	427	427
2 Fuel tank opening, cleaning, brazing and refitting (E/43)	1	Job	1148	1148
3 Radiator chockup removing by cleaning all the tubes, soldering the tubes with top and bottom removing and refitting (E/16)	1	Job	2163	2163
4 Silence/muffler repairing by removing, cleaning and refitting with welding work (E/56)	1	Job	717	717
5 Starter Armature Rewinding with material (EL/12)	1	Job	1148	1148
6 Steering unit overhauling (S/01)	1	Job	1007	1007
7 Front wheel <sup>Hub</sup> greasing including oil seal changing/NO. (W/06)	2	Job	430	860
8 Real wheel hub greasing including oil seal changing/No. (W/07)	2	Job	500	1000
9 King pin overhauling and refitting (S/07)	1	Job	1369	1369
10 Four spring leaf assy, removing, dismantling, recambering and refitting assy. (SD/01)	1	Job	2311	2311
11 Front mudguard damaged and rusted inner and outer wheel house new pieces welding, patching and finishing. (BD/12)	2	Job	1007	2014
12 Rear mudguard damaged and rusted inner and outer wheel house new pieces welding, patching and finishing. (BD/13)	2	Job	1007	2014
13 Front bumper removing repairing by welding, straightening, denting and refitting. (BD/03)	1	Job	1438	1438
14 Door locks removing repairing and refitting Door adjusting and setting/No. (BD/10)	2	Job	357	714
15 Branding on vehicle and front and rear number plate, flooring pieces patching and welding. (BD/18)	1	Job	2166	2166
16 <sup>Cabin</sup> Complete flooring rusted portion cutting and new flooring pieces patching and welding. (SC/03)	1	Job	2890	2890
17 Complete seat and back rest cushioning with coir foam 4" with u foam 2" with best quality rexine cover (SB/04)	1	Job	7227	7227
Rs = 27239			Total	30613.00
2451.51			CGST 9 %	2755.17
2451.51			SGST 9 %	2755.17
Total = 32142.02			Total	36123.34
Total Rs = 32142/-			Grand Total	36123

In words :- Thirty six thousand one hundred and twenty three only.)

  
R.S. Warpe  
(Section Engineer)

  
Deputy Engineer  
Mechanical Subdivision No.2  
Osmanabad.