

BUDGETARY OFFER

Tel/Fax:(020)-24267211

NO.EE/CGEDUNO3/T2/

Office of the Executive Engineer,
Chief Gate Erection Divisional Unit No-3,
Swargate, Pune-37

Dated :-

To,

- 1)
- 2)
- 3)

Sub :- Regarding Budgetary Offers.

Dear Sir,

With respect to above subject, you are requested to submit your budgetary offers for the work as per description given below for Somanthali Barrage, Tal. Phaltan, Dist. Satara. The rates should be inclusive of all taxes, duties, transportation, etc. The budgetary offers should be submitted to this office within 10 days during working hours.

Name of Work – Job work for manufacturing, supplying erecting & commissioning of electrical system required for operation of stop log gates gantry crane hoist 25T including material, labour charges etc. Complete job @ Somanthali Barrage, Tal. Phaltan, Dist. Satara.

Sr. No.	Name of Work	Qty	Rate	Amount
1	Budgetary Offer no. 17 for manufacturing, supplying erecting & commissioning of electrical system required for operation of stop log gates gantry crane hoist 25T including material, labour charges etc. Complete job @ Somanthali Barrage, Tal. Phaltan, Dist. Satara	1 Job		

TERMS AND CONDITIONS:-

- 1) Work is to be executed at Somanthali Barrage, Tal. Phaltan, Dist. Satara State - MAHARSHTRA
 - 2) Sealed and super scribed budgetary offers should reach in this office on or before 18/05/2018
 - 3) The rates quoted should be inclusive of all taxes, GST, duties, Transportation, insurances, other relevant state/central taxes, if any, etc.
 - 4) Completion period for the above work is three month from the date of Work order.
 - 5) The material should be as per relevant IS specification.
- Hence you are requested to furnish the lowest budgetary prices at the earliest.
- Thanking you,

(P.P. Deshmane)

Executive Engineer,

Chief Gate Erection Divisional Unit No-3,
Swargate, Pune-37

Copy submitted to the Superintending Engineer, Mechanical Circle, Kolhapur, for information & necessary action please. It is requested to upload this offer on official website of department.

Copy to Office Notice Board.

जलसंपदा विभाग (यांत्रिकी)

दरपत्रके - कामाचे अंदाजपत्रक तयार करणेकरीता सूचना क्रमांक १६, १७ सन २०१७-१८

कार्यकारी अभियंता, मुख्य द्वार उभारणी विभागीय पथक क्र. ३, पुणे-३७. दुरध्वनी क्र. (०२०) २४२६७२११ हे खालील दर्शविलेल्या कामकरिता नोंदणीकृत यांत्रिकी कंत्राटदाराकडून व मुळ साहित्य निर्मात्याकडून कार्यालयीन कामासाठी सर्व कर समावेशक अंदाजपत्रकीय दरपत्रके मागविण्यात येत आहेत. संबंधीतानी ही जाहीरात प्रसिध्द झाल्यापासून अंदाजपत्रकीय दरपत्रके दि. ११/०५/२०१७ पासून १८/०५/२०१७ पर्यंत कार्यालयीन वेळेत सादर कराव्यात. सदर बाबींचा सविस्तर तपशिल www.mahayantriki.gov.in या वेबसाईट वर उपलब्ध आहे.

अ. क्र	कामाचे नांव	परिमाण	दर	रुपये
१	Budgetary Offer No. 16 for manufacturing, supplying erecting & commissioning of electrical system required for operation of Vertical Lift Gate 15 x 8.33 mtr, 12 nos. Hoist 120T including material, labour charges etc. Complete job @ Somanthali Barrage, Tal. Phaltan, Dist. Satara.	1 Job		
२	Budgetary Offer no. 17 for manufacturing, supplying erecting & commissioning of electrical system required for operation of stop log gates gantry crane hoist 25T including material, labour charges etc. Complete job @ Somanthali Barrage, Tal. Phaltan, Dist. Satara	1 Job		

१. सदर अंदाजपत्रकीय दर सूचना वेब साईट www.mahayantriki.gov.in वर उपलब्ध आहे.
२. वरील सादर केलेली कामे अंदाजपत्रकीय कार्यवाहीसाठी असून प्रत्यक्ष कामाच्या आदेशाशी त्याचा काहीही संबंध नाही.

३
१५८

कार्यकारी अभियंता

मुख्य द्वार उभारणी विभागीय पथक क्र.३, पुणे-३७.

GOVERNMENT OF MAHARASHTRA
Water Resource Department
BUDGETARY OFFER NOTICE NO.-17 for 2017-18

Executive Engineer, Chief Gate Erection Divisional Unit No. 3 Swargate, Pune-37 (Phone No. 020 - 24267211) invites Budgetary Offer for manufacturing, supplying erecting & commissioning of electrical system required for operation of stop log gates gantry crane hoist 25T including material, labour charges etc. Complete job @ Somanthali Barrage, Tal. Phaltan, Dist. Satara.

A) Stop log gate, 2 sets, 25 T Gantry crane

1	Stop log gate, 25 T Gantry crane: Providing and installing protection panel consist of Main 125 A MCCB with three pole, 36 kA, Thermal Magnetic type (Ics=Icu=100%), 95A three pole power contactor, 150 Sq.mm. Copper bus-bar, Voltmeter with selector switch, A-meter with CT and selector switch, R, Y, B Indication lamp, Start/ Stop/ Emergency push button, Control transformer of 415/110 V AC, 1500 VA. All indicators and instruments should be protected by MCB. The penal should be floor mounted, free standing type, dust and vermin proof, penal should be prepared by CPRI manufacturer and must be suitable with IP 65.	Rs./Job
2	Stop log gate, 25 T Gantry crane: Panel should be suitable for outdoor application and it will be placed on crane platform, the panel will accommodate VFD for hoist motor (9.9 KW), The VFD should have 200% Starting torque for 1 Min. and should be equipped with dynamic braking system, input and output chock to be provided, VFD bypass system to be provided in order to operate the crane in case of VFD Failure. Necessary interlock and P B Should be provided to protective penal, contactors to be provided for EM Break and thrust break.	Rs./Job
3	Stop log gate, 25 T Gantry crane: LT - A reversible DOL starter to be provided for 2 No of LT Motor of HP each, the scheme should be designed such that both motors start and stop at the same time. Separate overload position should be provided for both motors. Necessary interlock and P. B. should be provided to protective penal, contactors should be provided for E M Break and Thruster Break.	Rs./Job
4	Stop log gate, 25 T Gantry crane: Lighting transformer: A lighting transformer is to be provided of 415/220 AC, 3KVA with enclosure and will be placed at operator cabin.	Rs./no.
5	Stop log gate, 25 T Gantry crane: Providing and erecting Sheet Steel powder coated MCB distribution board - flush / surface mounted fitted with bus bar, neutral link, earth bar and DIN rail, confirming to IS 13032 and BS 5486-1986 without MCB to house appropriate nos. of MCBs.(The DBs should be used of same company of MCB to be used) (E) Single phase 8 way single door.	Rs./Job
6	Stop log gate, 25 T Gantry crane: Cable Reeling Drum: The cable reeling drum should be spring operated bi-directional suitable to house for 3C X 10 Sq.mm. Cu, flexible, TRS/EPR cable. 25 meter.	Rs./no.
7	Stop log gate, 25 T Gantry crane: Junction Box to be provided at hoist trolley can connect should be at connector with all trolleys.	Rs./set
8	Stop log gate, 25 T Gantry crane: Plug and socket box: The boxes to TAP supply to GC across the complete span will be provide with the help to plug and socket box, the plug and socket box should have one no. of 32 A, 5 pin, IP 67 type, Terminal to be provide in the box loop in loop out type for power cable.	Rs./no.

9	Stop log gate, 25 T Gantry crane: 1. Hoist- Interlock for stopping at Extremely Top and bottom position at rotary gear limit switch must be provided. 2. LT- Interlock for stopping at extremely left and right position at rotary gear limit switch must be provided. 3. CT- Interlock for stopping at extremely Upstream and downstream position at rotary gear limit switch must be provided.	Rs./Job
---	---	---------


Interested Contractors/vendors are requested to submit the budgetary offer for above mentioned Job work/materials duly stamped & signed by competent authority.

The offer should be sent with following details specified separately for the supply details required:-

- 1) Basic price
- 2) GST
- 3) Freight charges
- 4) Discount (if any)
- 5) Other taxes such as VAT etc.
- 6) Delivery period
- 7) Validity of offer

Please Note:- Budgetary offer is invited only for the estimation purpose. It does not give any assurance regarding floating of tender of otherwise.

3
T.S.2.


 Executive Engineer
 Chief Gate Erection Divisional Unit no. 3
 Swargate, Pune-37