तात्काळ

प्रति.

मा. अधिक्षक अभियंता यांत्रिकी मंडळ नागपुर

विषय :-

बजेटरी ऑफर महायोजिकी संकेतस्थळावर <u>www.mahayantriki</u> प्रसिध्द करणेबाबत. बजेटरी ऑफर क्रमांक ३८ सन २०१८.

महोदय,

या पत्रासांबत पार्टावण्यात यंत असलेली बजेटरी ऑफर महायांत्रिकी संकेतस्थळावर प्रसिध्दीस देण्यात यांवी ही

विनंती.

8	कार्यालयाचे नांव	कार्यकारी अभियंता, उपसा सिंधन यात्रिकी विभाग क्र.१, भंडारा (एस.टी. वर्कशॉप समोर, नागपूर रोड, भंडारा).	
2	बजेटरी ऑफर महायांत्रिकी संकेतस्थळावर प्रसिष्दीची अंतीम तारीख	8/9/90/8088	

सहपत्र :-बजेटरी ऑफर (मराठी) प्रत्यको २ प्रती.

> कार्यकारी अभियंता, उपसा सिंचन यांत्रिकी विभाग क्रं.१ भंडारा.

## प्रतिलिपी :-

- १) उप अभियंता, उपसा सिचन योगिको उपविभाग क्रं. १ आंबाडी यांना माहितीस्तव अग्रेरिका.
- २) उप अभियंता, उपसा सिचन पात्रिको उपविभाग क्रे. २ गाँदिया यांना माहितीस्तव अग्रेधित.
- वप अभियंता, उपसा सिचन यांत्रिको व विद्युत उपविभाग क्रे.१, भंडारा यांना माहितोस्तव अग्रीधत.
- ४) उप अभियंता, योजिको अभियोजिकी कर्मशाळा उपविभाग क्र.१, भंडारा यांना माहितीस्तव अग्रेषित.
- ५) नोटीस बोडांबर लावण्यासादी.

## RATE PROFORMA

## GOVERNMENT OF MAHARASHTRA

## WATER RESOURCES DEPARTMENT

Bugetory Offer No.38

Issue Date - 17/01/2018 Closing Date - 24/01/2018 Opening date - 25/01/2018

Executive Engineer, Lift Irrigation Mechanical Division No.1, Bhandara

Sealed rates (excluding of GST) are invited from WRD registered contractor or OEM by the Executive Engineer, Lift Irrigation Mechanical Division No.1, Bhandara. (Phone No.07184-252166) for the purpose of estimation of the following works.

Name of the work - Design, Manufacturing, Supply, Erection, Testing, Commissioning of 40/5 MT capacity double girder E.O.T. crane for Dhapewada Stage-2 Lift Irrigation Scheme Dist. Gondia.

Est. Qty. may be	Unit	Description of Item	Unit Rate	Amount
1	unit	Item No. 1 - Providing, design, manufacturing, supply, transportation, erection, testing & commissioning of 40/5 MT capacity double girder pendent operated EOT crane as per specifications with microcontrol in main hoist, cross travel & longitudinal travel including all test at works having (c-c distance) span of 10.9 m, total lift for main hook-14 m & auxiliary hook-15 m		
82	m	Item No. 2 - supply, transportation, erection, testing & commissioning of crane rail type 135 lb/yard minimum to be fitted with intermittent sole plate, rail fixing clamp etc as per specification (both side of the pump house)		
40	m	Item No. 3 - supply, transportation, erection, testing & commissioning of four wire copper leads of 4 SWG, DSL system with all neccessory hardware insulator bracket suitable for above crane for 40 m bay length		
1	Kit	Item No. 4 - providing spare parts as per company's recommendation sufficient for the next two year after commissioning.	F- 1	***

Note - GST should be mentioned seperately for above items.

Executive Engineer
Lift Irrigation Mechanical Division No. 1
Bhandara.