

“जलसंपदा विभागाच्या संकेतस्थळावर कृपया भेट द्या -<https://wrd.maharashtra.gov.in>”

जा.क्र. / १५७९ /उसियांविक्र.२चंद्र / ताशा-२ / धा.क्र.४४ / ब.ऑफर / २०१७	कार्यकारी अभियंता यांत्रिकी उपसा सिंचन विभाग क्र.२, बाबुपेठ, चंद्रपुर - ४४२४०३ यांचे कार्यालय
☎ :- (०७१७२)२२७३८२	
फॅक्स :- (०७१७२)२२७३८२	
ई मेल :- mlidn2@rediffmail.com	दि. ०४ /०७ /२०१७.

प्रति,

मा. अधिक्षक अभियंता
यांत्रिकी मंडळ , नागपुर

विषय :- डोंगरगाव ठाणेगाव उपसा सिंचन योजना ता. आरमोरी जि. गडचिरोली

१० मे.टन इ.ओ.टी. क्रेनचे तसेच संलग्न घटक भागाचे संकल्पन,निर्मिती, पुरवठा ,
उभारणी,चाचणी व कार्यान्वितीकरण कामाची बजेटरी ऑफर संकेतस्थळावर प्रसिध्द
करणेबाबत.

महोदय,

या पत्रासोबत डोंगरगाव- ठाणेगाव उपसा सिंचन योजनेच्या पंपगृहात उभारणी करण्यात येणाऱ्या १० मे.टन
इओटी क्रेन तसेच संलग्न घटक भागाचे संकल्पन,निर्मिती, पुरवठा , उभारणी,चाचणी व कार्यान्वितीकरण
कामाची बजेटरी ऑफर क्रं. ७ / २०१७-१८ (GST चा अंतर्भुत करून) यांत्रिकी संघटनेच्या संकेतस्थळावर
(www.mahayantriki.gov.in) प्रसिध्द करण्यात यावी हि विनंती.

कार्यालय	कार्यकारी अभियंता, यांत्रिकी उपसा सिंचन विभाग क्र.२, चंद्रपुर
बजेटरी ऑफर प्रसिध्द करण्याची अंतिम तारीख	दि. १२.७.२०१७
बजेटरी ऑफर स्विकारण्याची अंतिम तारीख	दि. २६.७.२०१७.

सबब आपले माहिती व पुढील योग्य कार्यवाहीस्तव सविनय सादर.

सहपत्र :- बजेटरी ऑफर क्र. ०७ /२०१७-१८ — १ प्रत

कार्यकारी अभियंता
यांत्रिकी उपसा सिंचन विभाग क्र.२
चंद्रपुर

Budgetary Offer No.7/ 2017-2018

Name of Work:- Design, Manufacturing, Supply, Erection, Testing and Commissioning of 10 MT Crane with allied equipments at Dongargao Thanegaol L.I.S, Th. Armori Dist.:- Gadchiroli.

Budgetary Offers for estimation purpose are invited from the reputed Original EOT Manufacturers.

Qty.	Unit	Description of Items	Rate	Amount
1	Unit	Item No.1 (A) – E.O.T. Crane 10 MT Design , manufacturing , Providing, installing, Testing & commissioning of EOT of 10 MT capacity Double Girder pendent operated as per specification with micro control in main hoist , cross travel & longitudinal travel including all test at work having (C – C Distance) Span of 5 mtr. . Total lift for main Hook 12 mtr and for Auxillary Hook is 12 mtr. a) Crane Structure - As per IS 3177 & 807 b) Main Hoist - 10 MT c) Long Traverse – 10 mtr. d) Distance from Gantry to Pump Floor Level – 08 mtr. e) Distance from Pump Floor Level to Valve Floor Level – 04 mtr. f) Total No. of Gantry Girders – 02 Nos.		
20	Mtr.	Item No. 2 – Supply , Transportation , Erection, Testing and commissioning of gantry rails , type 90 lbs/yard minimum to be fitted with intermittent sole plate, rail fixing clamp etc. as per specification (both side of the pump house)		
10	Mtr.	Item No. 3 :- Supply , Transportation , Erection, Testing and commissioning of four wire copper leads of 4 SWG, DSL system with all necessary hardware insulator bracket suitable for above crane for 10 mtr bay length.		
1	lot	Item No. 4 :- Providing spare parts as per companys recommendation sufficient for the next two years after commissioning.		

Note :- Rates are inclusive all prevailing Taxes including G.S.T.

Executive Engineer
Mechanicle Lift Irrigation Dn.No.2
Chandrapur