

E-Mail – tembhumeunit@gmail.com
जा.क्र./टेंउसियांवविप/ताशा-३/ ४० /२०१६

Phone – (02164) 271142

कार्यकारी अभियंता,
टेंभु उपसा सिंचन यांत्रिकी व विद्युत पथक,
ओगलेवाडी, कराड यांचे कार्यालय
दिनांक:- ०७/०१/२०१६

प्रति,
जिल्हा माहिती अधिकारी,
जिल्हा माहिती कार्यालय,
३ रा मजला, नवीन प्रशासकीय इमारत,
सातारा. ४१५ ००१ (फोन नं. ०२१६२-२३७४४०)

विषय :- जाहीरात प्रसिध्दीस देणेबाबत.

महोदय,

सोबत जोडलेली जाहिरात वृत्तपत्रात प्रसिध्द करण्यासाठी पाठविण्यात येत आहे. कृपया ती नेमून दिलेल्या तारखेला किंवा तत्पूर्वी प्रसिध्दीस द्यावी, ही विनंती.

- १) कार्यालयाचे नाव, पत्ता व दुरध्वनी क्रमांक : कार्यकारी अभियंता, टेंभु उपसा सिंचन यांत्रिकी व विद्युत पथक, ओगलेवाडी, कराड पिन :- ४१५१०५, फोन नं : (०२१६४) २७११४२.
- २) जाहीरात प्रसिध्द होण्याचा अंतिम दिनांक : दिनांक १५/०१/२०१६ अथवा तत्पूर्वी
- ३) प्रसिध्दी कोणत्या स्तरावर आवश्यक (प्रादेशिक/जिल्हा पातळीवर) : जिल्हा स्तरावर (सातारा Region)
- ४) जाहीरातीचे बील कोणाच्या नावे पाठवावयाचे : कार्यकारी अभियंता, टेंभु उपसा सिंचन यांत्रिकी व विद्युत पथक, ओगलेवाडी, कराड
- ५) जाहीरात किती वृत्तपत्रात प्रसिध्द करावयाची व किती वेळा. : एक “क” वर्ग मराठी दैनिक व एका साप्ताहिक वृत्तपत्रात एकाचवेळी फक्त एकवेळा. (कमीत कमी जागेत.)
- ६) किती वेळा जाहिरात प्रसिध्द करावयाची आहे. : एकवेळा.

आपला विश्वासू

सोबत :- जाहिरातीच्या ४ प्रती.

कार्यकारी अभियंता
टेंभु उपसा सिंचन यांत्रिकी व विद्युत पथक,
ओगलेवाडी, कराड

प्रत :- मा.अधीक्षक अभियंता, यांत्रिकी मंडळ ,कोल्हापूर यांना माहितीसाठी व वेबसाईट प्रसिध्दीसाठी सविनय सादर.

जलसंपदा विभाग (यांत्रिकी)

अंदाजपत्रकीय दरपत्रके मागविण्यासाठीची दरपत्रके

कार्यकारी अभियंता टेंभू उपसा सिंचन यांत्रिकी व विद्युत पथक, कोयना सायडींग, ओगलेवाडी, कराड, ४१५१०५ (दुरध्वनी क्र.२७११४२) हे खाली दर्शविलेल्या कामाकरिता नोंदणीकृत यांत्रिकी कंत्राटदाराकडून व मुळ साहित्य निर्मात्याकडून कार्यालयीन कामासाठी अंदाजपत्रकीय दरपत्रके मागवित आहेत. संबंधितांनी हि जाहिरात प्रसिद्ध झाल्यापासून अंदाजपत्रकीय दरपत्रके दि. १५/०१/२०१६ पासून २१/०१/२०१६ पर्यंत कार्यालयीन वेळेत सादर करावीत. सदर कामाच्या बाबीचा सविस्तर तपशील www.mahayantriki.gov.in या वेबसाईट वर उपलब्ध आहे.

अ.क्र	तपशील	परिमाण	दर	रुपये
१.	टेंभू उपसा सिंचन टप्पा क्र १ब येथील व्ही.टी पंप क्र.५,१० व १२ च्या एच.टी.मोटर के.ई.एल.मेक १७०० के डब्लू डिसमेंटलींग करून डी.ई. व एन.डी.ई. बेअरींग बदलणे, मोटरचा स्टेटर व्ही.पी.एल प्रोसेस करणे, मॅग्नेटीक स्ट्रीप सव्हिसींग इ. कामे मटेरीयल ,मंजूरी,वाहतूक खर्च इ.	३ नग		
२	टेंभू उपसा सिंचन टप्पा क्र.१ब येथील किलॉस्कर मेक पंपाच्या ११०० एम.एम.डिलीव्हरी पाईपसाठी रबर बेलो एक्सपान्शन जॉईंट-७ नगाची निर्मिती,पुरवठा, डिसमेंटलींग , उभारणी इ. कामासह मटेरीयल ,मंजूरी,वाहतूक खर्च व टॅक्सेसह.	७ नग		
३.	टेंभू उपसा सिंचन टप्पा क्र. १अ येथील उर्ध्वनलीका क्र.४,५,६ वरील कायनेटीक एअर व्हॉल्व मधील सिझन टिंबर बॉल २०० एम.एम. व १०० एम.एम. प्रत्येकी २० नग, पॅकींग व नटबोल्टससह पुरवठा करणे व बसविणेचा खर्च, वाहतूक व टॅक्सेसह.	२० नग		
४	टेंभू उपसा सिंचन टप्पा क्र.१अ येथे लेव्हल टेस्टिंगसाठी, लेव्हल टेस्टिंग उपकरण , मॅग्नेटीक स्टॅंडसह पुरवठा करणे, कॅलीब्रेशन, टेस्टिंग इ. (Magnatic Level of Least Count 0.02 mm/meter) वाहतूक व टॅक्सेसह.	१ नग		
५	१)टेंभू उपसा सिंचन टप्पा क्र. १अ येथे साहित्य हाताळणीसाठी ५ टन क्षमतेची चेनपुली ब्लॉक-ट्रायपॉईंड सह भाडे तत्वावर पुरवठा करणे, वाहतूक खर्च व टॅक्सेससह. २) टेंभू उपसा सिंचन टप्पा क्र.३अ येथे ३२ व्ही.एम.एफ. पंपाच्या स्ट्रेनरसाठी ३ एम.एम. जाडीची जाळी पुरवठा करणे, बसविणे व वाहतूक खर्च व टॅक्सेससह.	४७ □□□□ ३ नग		
६	अ) टेंभू उपसा सिंचन टप्पा क्र.१ब,१अ,२,३ येथील ६.६ के व्ही एच.टी.मोटर फीडर, एच.टी.सॉफ्ट स्टार्टर, एच.टी. कॅपॅसीटर, एच.टी.मोटर इ.चा हेलदीनेस तपास□□, देखभाल व किरकोळ दुरुस्ती इ.चा मंजूरी खर्च मटेरीयल खर्च इ. ब) टेंभू उपसा सिंचन टप्पा क्र.१ब,१अ,२,३ येथील ४१५व्होल्ट एल.टी.पॅनेल , इ.चा हेलदीनेस तपास□□, देखभाल व किरकोळ दुरुस्ती इ.चा मंजूरी खर्च मटेरीयल खर्च इ. क) टेंभू उपसा सिंचन टप्पा क्र.१ब,१अ,२,३ येथील ४१५व्होल्ट रिमोट कंट्रोल पॅनेल इ.चा हेलदीनेस तपासणे, देखभाल व किरकोळ दुरुस्ती इ.चा मंजूरी खर्च मटेरीयल खर्च इ.	१ सेट प्रत्येकी १ नग प्रत्येकी १ नग प्रत्येकी		
७	टेंभू उपसा सिंचन टप्पा क्र १ब येथील व्ही.टी पंपाच्या एच.टी.पॅनेल फयुजेस ६.६ के.व्ही. २५० अ‍ॅम्पीअर ची निर्मिती करणे, पॅकींग व ट्रान्सपोर्टेशन खर्चासह पुरवठा करणे.	१० नग		

वरील कामासाठी सादर केलेली कामे अंदाजपत्रकीय कार्यवाहीसाठी असून प्रत्यक्ष कामाच्या आदेशाशी त्याचा काही संबंध नाही.

कार्यकारी अभियंता
टेंभू उपसा सिंचन यांत्रिकी व विद्युत पथक,
ओगलेवाडी, कराड

Office of the Executive Engineer,
Tembhu Lift Irrigation Mech. & Elect. Unit,
Koyna Siding, Oglewadi, Karad.
Dist-Satara. Pin- 415 105.
e-Mail : tembhumeunit@gmail.com
Date:

To,
M/s. 1) _____
2) _____
3) _____

Subject: - Regarding Budgetary Offers.

Dear Sirs,

With Respect to above subject, you are requested to submit your budgetary offers for the work as per description given below for Tembhu L.I.S. stage 1B, Tembhu Tq. Karad, Dist-Satara. for Kirloskar make H.T. motor 1700/2279 KW/HP, 750RPM/50 HZ, 177 Amps. CACW, Insulation Class F. The rates should be inclusive of all taxes, duties, transportation, etc. The budgetary offers should be submitted to this office within 07 days during working hours

Sr.No	Description	Qty	Rate	Amt
1)	Repairs to HT Motor. To carry out the job work required for replacement of NDE & DE bearing, general servicing, stator motor VPL, magnetic strips servicing etc. complete job including disassembling, assembling, including labour, material, workshop charges, sundry material, handling, transportation to & fro test & trial at site, etc. complete job for 6.6 KV, 750 rpm, 50Hz, 2279 HP/1700KW, 177 Amps, CACW Insulation class F, Kirloskar electrical limited, make HT Motor of VT Pump NO.5, 10 & 12 @ Tembhu LIS Stage 1B.	3 job		

Thanking you.

Yours Faithfully,

(P.P.Deshmane)
Executive Engineer
Tembhu Lift Irrigation Mech. & Ele. Unit,
Oglewadi, Karad.

Copy Submitted to Superintendent Engineer, Mech Circle, Kolhapur, for information & requested to publish this offer on official site of mahayantriki.

To,
M/s. 1) _____
2) _____
3) _____

Subject: - Regarding Budgetary Offers.

Dear Sirs,

With Respect to above subject, you are requested to submit your budgetary offers for the work as per description given below for Tembhu L.I.S. stage 1B, Tembhu, Tq.Karad, Dist-Satara. The rates should be inclusive of all taxes, duties, transportation, etc. The budgetary offers should be submitted to this office within 07 days during working hours.

Sr.No	Description	Qty	Rate	Amt
1)	Manufacturing, Providing, Testing of Rubber expansion Joint To carry out the manufacturing, providing, testing of handling etc. complete only, rubber bellows expansion joint 7 Nos. of Kirloskar make BHR 95,2200 HP, VT Pump @ Tembhu LIS stage 1B and testing of rubber expansion joints in pump delivery pipe line complete suitable for following specification a) Diameter – 1100mm, b) internal test pressure – 24 bar, c) Vacuum test pressure mm of mercury- 700 mm d) OD – 1355 mm e) PCD- 1270 mm, f) Width – 350 mm, g) Thickness of rubber – 30 mm, h) No.of holes – 32 nose, i) dia. of holes – 44 mm, including moulding pattern, arrangement of holes etc. complete job for Tembhu LIS Stage 1B.	7 jobs		
2	Loading unloading @ site transporation to Tembhu 1B site approx 400 Km.	400 KM		
3	Dismantling of damaged rubber expansion joint on delivery line of diam.1100mm & fitting new rubber expansion joint on the same delivery line of V.T. pump @ Tembhu 1B site.	7 Jobs		

Thanking you.

Yours Faithfully,

(P.P.Deshmane)

Executive Engineer

Tembhu Lift Irrigation Mech.& Ele.Unit,

Ogalewadi, Karad.

Copy Submitted to Superintendent Engineer, Mech Circle, Kolhapur, for information & requested to publish this offer on official site of mahayantriki.

To,
M/s. 1) _____
2) _____
3) _____

Subject: - Regarding budgetary offers ...

Dear Sirs,

With Respect to above subject, you are requested to submit your budgetary offers for the work as per description given below for Tembhu L.I.S. stage 1A, Tembhu, Tq.Karad, Dist-Satara. The rates should be inclusive of all taxes, duties, transportation, etc. The budgetary offers should be submitted to this office within 07 days during working hours.

Sr.No	Description	Qty	Rate	Amt
1)	job work required for manufacturing, providing, installing seasoned timber ball covered with rubber, packing, Bolts etc. complete for 200mm IVC make Kinetic air valve as per specification on delivery pipe & rising main including material, moulding pattern, labour, workshop, sundry charges etc. complete job for Tembhu LIS stage 1A for rising main No. 4,5,6. 1) make of air valve – IVC/BSJ-SHAU/Equivalent. 2) Type of air valve- double orifice kinetic type 3) Size of air valve-200mm 4) class- PN1.0 5) Working Pressure- 10Bar 6) Test pressure-15 bar. i) Small orifice float-seasoned timber ball covered with soft rubber ii) Large orifice float- seasoned timber ball covered with hard Valcanite rubber iii) packing dexine seat ring. Bing. Big float iv) packing for small float iv) Removing & refitting for above work	20 20 20 20 20		
2.	Job work of PROVIDING & SUPPLYING, checking & submitting calibration certificate, Testing, including service charges and all taxes, Transportation etc. complete job. For following level testing equipments & alignments checking instruments along with measuring like magnetic stand at Tembhu LIS.ST IA. Pump house.			
I	Cast iron I – section straight edge 1500mm lg.as per IS 5268-1991 GRADE -1	1 No		
II	MASTER LEVEL of least count 0.02 mm/miter.	1 No		
III	MAGNETIC STAND suitable for dial indicator having following parts 1) magnetic stand 2) level 3) pole 4) support rod 5) support rod assly 6) clamp knob 7) dial indicator mount hole 8) lug fixture 9) fine adjustment knob 10) bushing	1 No		
IV	DIAL INDICATOR with least count 0.01mm capacity up to 10mm.	1 No		

The budgetary offers should reach to this office within 10 working days from issue of this notice.

Thanking you.

Yours Faithfully,

(P.P.Deshmane)

Executive Engineer

Tembhu Lift Irrigation Mech.& Ele.Unit,

Ogalewadi, Karad.

Copy Submitted to Superintendent Engineer, Mech Circle, Kolhapur, for information & requested to publish this offer on official site of mahayantriki.

To,
M/s. 1) _____
2) _____
3) _____

Subject: - Regarding Budgetary Offers.

Dear Sirs,

With Respect to above subject, you are requested to submit your budgetary offers for the work as per description given below for Tembhu L.I.S. stage 3A,Tembhu The rates should be inclusive of all taxes, duties, transportation, etc. The budgetary offers should be submitted to this office within 07 days during working hours

Sr.No	Description	Qty	Rate	Amt
1)	Providing 5T cap chain pulley block& Tripoid Arrangement- 2 sets on Tembhu Stage -3A site on rent day basis including transportation & all taxes	47 Days		
2)	Manufacturing, providing 3mm thick G.L crimped type wire mesh & fitting to the 32" VMF V.T. pump strainer of size Ø 1550X600mm around & bottom of strainer having square opening 25mm uniform in size including all taxes	3 nos.		

Thanking you.

Yours Faithfully,

(P.P.Deshmane)
Executive Engineer
Tembhu Lift Irrigation Mech.& Ele.Unit,
Ogalewadi, Karad.

Copy Submitted to Superintendent Engineer, Mech Circle, Kolhapur, for information & requested to publish this offer on official site of mahayantriki.

To,
M/s. 1) _____
2) _____
3) _____

Subject: - Job work of Checking healthyness and attending routine maintenance & minor repair works of 6.6 kV rated HT. Equipments such as HT Motor Feeder, HT Soft Starter, HT Capacitor, LT Panel & Remot control Panel.

Dear Sirs,

With Respect to above subject, you are requested to submit your budgetary offers for the work as per description given below for Tembhu L.I.S. stage 1A,1B,2,3 pump House. The rates should be inclusive of all taxes, duties, transportation, etc. The budgetary offers should be submitted to this office within 07 days during working hours.

Sr. No.	Description	Qty.	Rate / Unit in Rs.	Total in Rs.
1	<p>Checking healthyness and attending routine maintenance & minor repair works of 6.6 kV rated HT. Equipments such as HT Motor Feeder, HT Soft Starter, HT Capacitor, HT Motor as per requirement with necessary technically skilled manpower, tools & tackles, testing instruments, small consumables such as cotton waste, cleaning cloth, cleaning oil, insulation tape etc.</p> <p>Scope of work as below –</p> <p>Incomer & Motor Feeder Panel</p> <p>Cleaning of Panel, Cleaning of Busabar, Tightening of Busabar Joints, Checking Alignment of Vacuum Contactor Trolley ie Fix & Finger Contacts, Checking ON/OFF Operations of Vacuum Contactor, Checking IR Values of Vacuum Contactor, Checking Vacuum Contactor Interrupters with Megger In OFF Position, Checking Continuity of HT Fuses of VC Trolley, Tightening of all Control Wiring Connections of Motor Feeder Metering Chamber, Tightening of Control Cable & Power Cable Connections, Checking of Helthiness of Motor Protection Relay with Trip Test provided in Test Programme of MPR, Checking all indications with 220V DC Control Supply, Checking Functional Tests at Local & Remote Position, Checking Emergency Stop Function, Checking all Safety interlocks as per Wiring Diagram of Motor Feeder.</p>	18 Set		
2	<p>Softstarter Panel</p> <p>Checking HT Soft Starter with 230V AC Control Supply, Checking all interlocks with Main HT Motor Feeder, Checking By pass Device Continuity, Checking Timer Operations, Checking IR Values with Megger, Tightening all Control & Power Cable Connections of HT Soft Starter & HT Motor, Checking IR Values of HT Motor, Checking Motor Space Heater Connection & interlock with Main Motor Feeder with 230V AC</p>	18 Set		

3	Supply ie Heater Supply should cut Off when Main Motor Feeder ON Position. Capacitor Bank Checking ON/OFF Operations of Capacitor Panel Isolator, Checking Continuity of HT Fuses of Capacitors, Checking IR Values of Capacitor Bank, Checking Capacitors with 415V 3 Phase LT Supply, Measuring 3 Phase Currents with Digital Multimeter (Result- All 3Phase should have Same Current)	18 Set		
4	L T Panel	1 Set		
5	Remot Control Panel For Tembhu stage -1A	1 Set		

Thanking you.

Yours Faithfully,

(P.P.Deshmane)

Executive Engineer

Tembhu Lift Irrigation Mech.& Ele.Unit,

Ogalewadi, Karad.

Copy Submitted to Superintendent Engineer, Mech Circle, Kolhapur, for information & requested to publish this offer on official site of mahayantriki.

To,

M/s. 1) _____
2) _____
3) _____

Subject: - Regarding Budgetary Offers.

Dear Sirs,

With respect to above subject, you are requested to submit your budgetary offers for the work as per description given below for Tembhu Lift Irrigation Stage 1B, Tembhu Tal : karad Dist- satara. For Manufacturing, providing of H.T. fuses 250 Amp, 6.6 KV.

1) Manufacturing, providing of H.T. fuses 250Amp, 6.6 KV.

Sr.No	Description	Qty	Rate	Amt
1	Name of work:- Job work of Manufacturing, providing & supplying of H.T. panel fuse of 6.6 KV.250 Amp with packing, forwarding, transportation charges for V.T. pump No.4,8,11 & 17 @ Tembhu Lift Irrigation Stage 1B.	10 Nos.		

The budgetary offer should be reach this office within 10 days from the date of publication during working hours.

These offers are required for office work only No work orders will be issued in connection to these offers.

Please do the needful.

Thanking you.

Executive Engineer
Tembhu Lift Irrigation Mech.& Ele.Unit,
Ogalewadi, Karad.

Copy Submitted to Superintendent Engineer, Mech Circle, Kolhapur, for information & requested to publish this offer on official site of mahayantriki

Copy Notice Board.

