

**Government of Maharashtra
Water Resources Department
Superintending Engineer, Mechanical Circle, Kolhapur**

Budgetary offer for the following work (*Non DSR items*) are invited by the Executive Engineer, Mechanical Division, Satara-415003 Phone No. 02162-246029 on behalf of Governor of Maharashtra for estimation purpose from the reputed Manufacturers/Suppliers.

The Government of Maharashtra, Water Resources Department, has undertaken the work of Manufacturing & erecting Rail Pad @ N.O.F. Section for Goliath Crane, Extention Platform infront of CDU Of 115 MT - 5 Nos. Hoist & 40 MT - 3 Nos. Hoist , Cabin for all CDU , Extention to Guide Tee Upto Double the Gate Height & Locking arrangement @ Jihe Kathapur Barrage Tal - Koregaon, Dist- Satara.

It is requested to send the budgetary offer mentioning item wise rates with rate analysis for the same. The rates should without GST and duties. The offer should reach this office within 10 days with effect from **Dt.11.06.2021 to Dt.18.06.2021** on **email./ by post/ by hand** Further it is requested to forward relevant Technical literature, brochures of equipments and your comments if any.

Sr. No.	Description	Rate/ Unit.
1	Mapping of Steel reinforcement in pier & marking including manufacturing, installation & Dismantling of temporary scaffolding for above Process .	
2	Core Cutting of Size Dia.50 X 700mm For Anchors & Supply & erecting Anchors of Size Dia.36 X 1000mm long & Application Of Chemicals including manufacturing & installation of temporary scaffolding for above Process	
3	Erection Of Walkway bridge at site with the help of Suitable Capacity of Crane including Dismantling of temporary scaffolding for above Process.	

This information is required for the purpose of framing of working estimates and hence the urgency. This Budgetary offer is also available on website www.mahayantriki.org Bidder is requested to act in given time frame.

No.MDS/PB-2/JK Barrage /1634 /of 2021
Office of the Executive Engineer,
Mechanical Division,
Krishnanagar, Satara PIN- 415003
Phone/fax No.02162/246029
e-mail eemdsatara@gmail.com
Date: 09.06.2021

-sd-
(A.R.Kalmegh)
Executive Engineer
Mechanical Division, Satara

SCHEDULE

Manufacturing & erecting Rail Pad @ N.O.F. Section for Goliath Crane, Extension Platform in front of CDU Of 115 MT - 5 Nos. Hoist & 40 MT - 3 Nos. Hoist , Cabin for all CDU , Extension to Guide Tee Up to Double the Gate Height & Locking arrangement @ Jihe Kathapur Barrage Tal - Koregaon, Dist- Satara.

Sr. No.	Description	Rate/ Unit.
1	Mapping of Steel reinforcement in pier & marking including manufacturing, installation & Dismantling of temporary scaffolding for above Process .	
2	Core Cutting of Size Dia.50 X 700mm For Anchors & Supply & erecting Anchors of Size Dia.36 X 1000mm long & Application Of Chemicals including manufacturing & installation of temporary scaffolding for above Process	
3	Erection Of Walkway bridge at site with the help of Suitable Capacity of Crane including Dismantling of temporary scaffolding for above Process.	

Conditions:

1. The attachment provided should have specifications as per schedule.
2. Rate should be quoted with separate GST.
3. Trial operation will be of minimum 100 hrs and rates should be quoted accordingly.
4. The necessary training is to be provided to concerned staff.

-sd-

(A.R.Kalmegh)

Executive Engineer
Mechanical Division, Satara