


**SCHEDULE 'B'**

**Name of Work :-** Providing and applying Primer and then Painting including surface preparation, chipping the welding, cleaning spatters, dust etc. of Gate Leaf Size 1.5x1.5 mtr & Embedment Structure, Trashrack Panel & Embedment Structure, Lifting Beam & Hoisting A frame Structure, approach platform chequered plate and Providing 5 Ton Chain Pulley and Greasing of Hoist and Gate Parts @ Haldipurani Lift Irrigation Scheme Ta - Chamorshi, Dist - Gadchiroli under Executive Engineer, Gadchiroli Irrigation Division, Gadchiroli.

| Sr. No.   | Description   | Quantity | Unit | Rate      | Amount           |
|---|---|----------|------|-----------|------------------|
| 1   | 2   | 3        | 4    | 5         | 6                |
|   | <b>Canal gate having size 0.3 x 0.3 mtr - 15 nos</b>  |          |      |           |                  |
| 1   | Providing and applying Primer and then Painting including surface preparation, chipping the welding, cleaning spatters, dust etc. of Gate Leaf Size 1.5x1.5 mtr & Embedment Structure. Painting Area =58.384 Sqmtr  | 1        | No   | 27531.06  | 27531.06         |
| 2   | Providing and applying Primer and then Painting including surface preparation, chipping the welding, cleaning spatters, dust etc. of Hoist Assy. Painting Area = 49.791 Sqmtr   | 1        | No   | 23478.70  | 23478.70         |
| 3   | Providing and applying Primer and then Painting including surface preparation, chipping the welding, cleaning spatters, dust etc. of Trashrack Panel & Trashrack Embedment Structure. Painting Area = 63.648 Sqmtr.   | 1        | No   | 30012.97  | 30012.97         |
| 4   | Providing and applying Primer and then Painting including surface preparation, chipping the welding, cleaning spatters, dust etc. of Lifting Beam and Hoisting A Frame & approach Platform Chequered plate. Painting Area = 158.647 Sqmtr.                      | 1        | No   | 74810.01  | 74810.01         |
| 5   | Cleaning Square Threaded Stem Rod of Screw Stem Hoist 10 MT to 15 MT capacity - 1 No, by cleaning agent. Applying M.P. Grade Grease - 5 kg to Threaded Portion and thrust bearings and Greasing of rollers (4 Nos.) Complete job with material & Labour charges | 1        | No   | 4785.38   | 4785.38          |
| 6   | Providing, erecting triple spur gear type Chain Pulley Block suitable for 5 Ton capacity.   | 1        | No   | 112676.61 | 112676.61        |
| 7   | Transportation of Fabricated Material by 4MT cap tempo.   | 1        | Trip | 6201.40   | 6201.40          |
|   | <b>Total Rs.</b>  |          |      |           | <b>279496.12</b> |
|   | <b>Add 18% GST</b>  |          |      |           | <b>50309.30</b>  |
|   | <b>Total Rs</b>   |          |      |           | <b>329805.42</b> |
|   | <b>Say Rs.</b>  |          |      |           | <b>329805.00</b> |
| <b>(Rs.Three Lakh Twenty Nine Thousand Eight Hundred &amp; Five Only)</b> |   |          |      |           |                  |

**Note :-** As per Govt. of Maharashtra P.W.D.Govt. Circular No. 2017/CR 121( Part -II) Building -2 mantralay, Mumbai -400032 Dated :- 19 / 09/ 2017 , The GST will be paid extra on Production of G.S.T.Paid Invoice Bill.

  
 ( V.R. Pradhan )  
 Executive Engineer  
 Mechanical Engineering Workshop Division,  
 Nagpur