

ABSTRACT

Name of Work: Repairs to travel device of TATA Hitachi Zaxis 120H Excavator Sr. no. 51578 for both the sides by way of replacing following spares as per O.E.M. Specification and part nos. with cost of material and labour charges etc.complete job.


Sr.No.	Description	Qty.	Rate	Amount
1	Repairs to travel device of TATA Hitachi Zaxis 120H Excavator Sr. no. 51578 for both the sides by way of replacing following spares as per O.E.M. Specification and part nos. with cost of material and labour charges etc.complete			
	Cost of spare parts	1	142558	142558
	Cost of labour	1	8580	8580
			Total =	151138.00
			G.S.T. 18% =	27204.84
			Total	178342.84
			Say =	178343.00


(In Words:- Rs. . . One lakh seventy eight thousand three hundred forty three only).

CERTIFICATE

Certified that,


- 1- Repairs are essential to keep machine in good working condition.
- 2- Spares are not available in dept. stores.
- 3- Such type of repair jobs are not carried out in our work shop due to lac of facilities.
- 4- Rates are reasonable.
- 5- Certify that the above repairs work is to be carried out immediately as the Dozer is urgently required on Project Canal Earth Work.


Shri. B.V. Satpute,
Sect. Engr.


(Shri. C.T. Satpute)
Deputy Engineer,
Mechanical Sub Division No.3
Osmanabad

sanctioned Estimate No.....the year. 2020-21
Estimate technically Sanctioned for Rs.

Rs. In Word.. One Lakh Seventy Eight Thousand Three Hundred
Forty Three only.



Executive Engineer
Mechanical Division
Osmanabad


Measurement sheet

Name of Work : Repairs to travel device of TATA Hitachi Zaxis 120H Excavator
Sr. no. 51578 for both the sides by way of replacing following spares as per O.E.M.
Specification and part nos. with cost of material and labour charges etc.complete
job.

Sr.No.	Description		Qty.	Rate	Amount
1	Removing travel device from travel device support and refitting it after completion of repair work A/13/1		2	1650	3300
2	Dismantling travel device, inspecting all the parts, removing damaged parts and refitting new parts as per OEM specification i.e. overhauling of travel device A/13/11		2	2640	5280
3	Replacing the following spares of the travel device				
3.1	4110369	Seal group	2	32801	65602
3.2	4321887	Bearing roller	4	18355	73420
3.3	J931640	Bolt	8	94	752
3.4	J931660	bolt	8	348	2784
				Total =	151138.00
				G.S.T.18%	27204.84
				Total =	178342.84
				Say=	178343.00

(In Words:- Rs. One lakh seventy eight thousand three hundred forty three only).


Shri. B.V.Satpute,
Sect. Engr.


(Shri. C.T.Satpute)
Deputy Engineer,
Mechanical Sub Division No.3
Osmanabad