

**MAHARASHTRA KRISHNA VALLEY DEVELOPMENT CORPORATION PUNE
411011(A GOVT. OF MAHARASHTRA UNDERTAKING)**

Rates for the supply of Horizontal Submerged Centrifugal Pump of 294 HP X 3 Nos with allied Electromechanical equipments as shown below at Agalgaon-Jakhapur LIS, Tal- Kavathemahankal, Dist- Sangli are invited from contractors having experience of the said work for estimate purpose. Please submit the rate & G. A. Drawing to The Office of Executive Engineer, Takari Mechanical & Electrical Division, Warnali, Sangli 416415 Maharashtra. within 10 days from the date of publishment.

Name of work :- Design, Manufacturing, supply, erection, testing & commissioning of submerged centrifugal pumps of 294 HP x 3 Nos. with allied electromechanical equipments etc at Agalgaon-jakhapur, Tal- Kavathe mahankal, Dist. - Sangli.

Item No.	Description	Qty.	Unit
1	Horizontal Submerged Centrifugal Pump-294HP Design, Manufacturing, Supply, erection, testing & commissioning of submerged centrifugal pumps with motor, multi vane enclosed type, complete with strainer, impeller assembly, base frame Foundation, 90 degree bend (pump discharge side), etc And giving test to full capacity. Suitable for following duties:	3	No
	a) Duty point discharge per pump = 0.2126 M ³ /sec.		
	b) Duty point head = 81.85 Mtr.		
	c) Maximum rpm synchronous = 1500		
	d) No. of stages = 2 stage		
	e) Max. No of pumps working in parallel = 3		
	f) Motor Capacity (including 20% power margin) = 335 KW		
	g) Voltage rating = 415 Volts		

This information is required for the purpose of framing of working estimates and hence the urgency. This Budgetary offer is also available on website www.mahayantriki.gov.in

Executive Engineer,
Takari Mech. & Elect. Division,
Sangli