## BUDGETARY OFFER

Name of Work: Design, Manufacture, Supply, Erection, Testing and Commissioning of 3 Nos. of Vertical Turbine Pump set of 325 HP with allied Electro-Mechanical equipments complete for already existing pump house of Siddheshwar Lahanshahada LIS Stage - 1. Tal., Dist.: Nandurbar

allied	Illied Electro-Mechanical equipments complete for already existing pump house of Siddheshwar Lahanshahada LIS Stage - 1 , Tal., Dist.: Nandurbar							
Sr.	Description	Qty.	Unit	Design, Manufacture & Supply		Total Amount in INR		
No.	Description	Giy.		Unit Rate in INR	Total in INR	Total Amount MTNR		
	Vertical Turbine Pumps Providing and installing at site of works and giving test to full capacity, vertical turbine pumps non-pull out type, complete with Strainer, Suction Bell, Column Assembly, Discharge Head, Motor Stool, Flexible Coupling, Sole Plates, Non-reverse Ratchet Arrangement etc. suitable for following duties and specifications.  1) Duty point Discharge per Pump = 285 lps 2) Duty point Head = 59.50 m 3) AHFL of River = 76.23 4) FSL of Master Chamber = 103.62 5) M.D.D.L. = 57.750 6) Pump Floor Level = 97.23 7) Centre Line or Delivery Pipe = 97.43 8) Length of Rising Main PSC/ RCC = 4441 Mtr. 9) Rising main Dia. = 800 mm 10) Delivery Pipe Dia. 400 mm 11) Efficiency (a) Bowl Efficiency = 85 %	3	Nos.					
	Providing & installing at site of works and testing of Cast Iron, Non-Slam, Double Flanged type Non Return Valve with by pass arrangement complete, suitable for following duties & specifications and as per IS 5312 (Part II-1986) Diameter = 400 mm PN Rating = 1.6 Working Pressure = 6.0 Kg/cm <sup>2</sup> Differential Pressure = 6.0 Kg/cm <sup>2</sup> Maximum Working Pressure = 12 Kg/cm <sup>2</sup>	3	Nos.					

3	Butterfly Valve Providing & installing at site of works and testing double flanged Butterfly Valves conforming to relevant IS/BS 5155 with Electric Actuator with 415 V A.C. Motors, D.O.L. Starting etc. complete, suitable for following duties & specifications.  Diameter = 400 mm PN Rating = 1.6 Working Pressure = 6.0 Kg/cm² Differential Pressure = 6.0 Kg/cm² Maximum Working Pressure = 12 Kg/cm²	3	Nos.		
4	Kinetic Air Valve Providing & installing at site of works and testing KAV (with isolating Sluice Valve) of Dia. 50 mm, PN 1.6 for releasing air from Delivery Pipes. Working Pressure = 6.0 Kg/cm <sup>2</sup>	3	Nos.		
5	Air Cushion Valve 200 mm Dia.	1	No.		
	Working Pressure = 6.0 Kg/cm <sup>2</sup>				
	Differential Pressure = 6.0 Kg/cm <sup>2</sup>				
	Maximum Working Pressure = 12 Kg/cm <sup>2</sup>				
6	Delivery Pipe Providing & jointing at site of works and testing delivery pipeline including jointing of all in between Valves upto Rising Main/Manifold complete, suitable for following duties, specifications. Diameter (NB) = 400 mm Wall Thickness = 8 mm Hydraulic Test Pressure = 16 Kg/cm2	90	Mtr.		
7	Dismantling Joints Providing & installing at site of works & testing of Dismantling Joints in pump delivery pipeline complete conforming to the following specifications. Diameter (NB) = 400 mm Wall Thickness = 10 mm Hydraulic Test Pressure = 16 Kg/cm2	3	Nos.		
8	L.T. Induction Motor  Providing & installing at site of works and testing to full capacity, solid shaft, squirrel cage Indution Motors CACW type 'F' class insulation suitable for operation on voltage mentioned below- 3 phase, 50 Hz with voltage variation of +/-6% and frequency variation +/-3% suitable for direct coupling with pumps under item No. 1 as per latest revision of IS 325, IS 4722 & other Relevant IS specifications. Suitable for following duties, specifications & conforming to detailed specifications.  Operating Voltage 415 kV Minimum kW Rating of Motor 250 kW Maximum Syn. Speed 1500 RPM	3	Nos.		
9	FCMA Soft Starter ATS Starter suitable for above Motor and as per relevant IS standard.	3	Nos.		
10	Cubical Capacitors 415 V, 3 Phase, 50 Hz Capacitor cubicles for the Motors to improve the power factor to .95. The KVAR capacity of the capacitors should not exceed the magnetizing KVAR of above motor.	3	Nos.		

## BUDGETARY OFFER

Name of Work: Design, Manufacture, Supply, Erection, Testing and Commissioning of 3 Nos. of Vertical Turbine Pump set of 325 HP with allied Electro-Mechanical equipments complete for already existing pump house of Siddheshwar Labarshahada LIS Stage - 1 Tal. Dist: Nandu

allied	allied Electro-Mechanical equipments complete for already existing pump house of Siddheshwar Lahanshahada LIS Stage - 1 , Tal., Dist.: Nandurbar						
Sr. No.	Description	Qty.	Unit	Design, Manufacture & Supply		Total Amount in INR	
				Unit Rate in INR	Total in INR	Total Amount in Tikk	
10	L.T. Distribution Panel (Suitable for above Pump house & Lightining For Indoor & Outdoor etc.)	1	Job.				
11	Temp. Scanner Panel Providing, installing at site of works& testing of Temperature Scanner Panel comprising of 3 Nos. Microprocessor Temperature Scanners having 10 point each to monitor Motor windings and Bearing Temperature, complete.	1	No.				
	Preparation of Cable Schedule and Supply, Installation, Testing of Cables. Providing, installing & energizing at site of works & testing suitable LT Control Cables & Wires, Cable Trays, Racks complete as required for the all above electrical equipments in Pump House.	1	Job.				
	Earthing Providing, installing at site of works Earthing comprising of adequate No. of Earth Stations, Earth Bars & individual double earthing to all electrical equipments as per detailed specifications.	1	Set				
	Water Level Indicator Providing installing at site of works and testing Water Level Indicators operating on 230 V, 50 Hz, A.C. supply and as per detailed specifications.	1	Set				
15	Spares & Tools Providing installing at site of works, Spares and Tools complete as per detailed specifications.	1	Set				
16	Testing, Commissioning, Trials and Operations for pumping machinery and performance testes and training to Departmental Staff and as per detailed specifications.	1	Job.				
	Providing and installing Fire Fighting System for the Pump House. Adequate Fire Fighting System for complete Pump House and Control Room as per latest Fire Norms/Guidelines for Safety issued by Central Electricity Authority confirming to IE rule No. 43,44,45 of 2005 specifications.	1	Job.				
18	Chain Pulley Block 5T Capacity With 30 Mtrs. Lift	2	Job.				
	TOTAL in INR					1	