

Abstract

Repair and Maintenance of double hoist type Canal VL Gates (2.5 x 2.5 m-03 Nos) by Way of Dismantling, Replacing/rectifying damaged sub-parts and refitting the same with proper alignment, Test and Trial. Complete job with material, labour & transportation charges. @...at Palkhed LBC KM 96 m Tal-Yeola, Dist. Nashik

Item	Description	Qty	Unit	Rate	Amount Rs
Item No.1	Fabrication & Erection of temporary A frame in std sections & foundation plates for dismantling of gate leaf for necessary repairs on site.	1	Nos of jobs	20963.49	20963.49
Item No.2	Labours charges for a team of Fitter, Welder, Mechanic, Electrician & helpers etc for Dismantling of hoist, gate leaf, from slot & Cleaning and completely for repairs complete job	18	man days	4545.00	81810.00
Item No.3	Sundry Material for Dismantling of gate leaf removing and cleaning for repairs with refitting of hoist & gate leafs etc complete.	1	Nos of jobs	39923.84	39923.84
Item No.4	Applying double coats of red oxide primers and two coats of anticorrosive epoxy black painting charges for all 3 Canal Regulating gates	1	Nos of jobs	77225.34	77225.34
Item No.5	Repairs job for repairing to similar screw stem hoist assy complete job of Canal Regulating gates 2.5 x 2.5 m (03 Nos)	1	Nos of jobs	464932.50	464932.50
Item No.6	Transportation charges for materials, Labours and equipments on site by 6 MT truck from nearest district place Nashik to Yeola to site PLBC KM96	1200 800	km	42.42	50904.00 33936
				716956.15 Rs	749394.17
	Add 0.5% Insurance			3585	0.5%
	Add 9 % CGST			64526	9%
	Add 9 % SGST			64526	9%
	Total cost of work			849593	Rs. 888031.00

Section Engineer
Gate Erection Subdivision Nashik

Deputy Engineer
Gate Erection Subdivision Nashik

Recommended for sanction for
Rs-888031/-

(S. A. Lakhe)
Executive Engineer
Chief Gate Erection Unit No. 5
Nashik - 4.

SANCTIONED

Vide Sr. No.....
Sanctioned Estimate
Register for the Year 20
for Rs. 88,49,593/-

(Rs. Eight lacs forty nine thousand -
five hundred ninety three only)

(Nitin Pote)

Superintending Engineer
Mechanical Circle, Nashik