

Government of Maharashtra
Water Resources Department
Superintending Engineer, Mechanical Circle, Kolhapur.

Budgetary offers for the following work (Non DSR items) are invited by the Executive Engineer, Mechanical Division, Kolhapur -416003 Phone No. 0231-2651284 on behalf of Government of Maharashtra for estimation purpose from the reputed Companies/Agencies /Contractors /Dealers. The State Government has taken up the work of erection of Zero Velocity Valves for Urmodi Lift Irrigation Scheme Stg II, R.M. 3 @ Kombadwadi, Tal. Koregaon, Dist- Satara.

The details and general specifications of site needed for design, manufacturing & supplying of Zero Velocity Valve (2400 mm, PN 1.6), required as anti-surge device will be made available if required in the Division Office. Interested Agencies are requested to go through the details and send the budgetary offers for proposed work of supply. The rates to be quoted must be excluding taxes and applicable all taxes must be mentioned separately. All other related additional technical points, any technical suggestions required to be included or removed in the description below in favour of efficient and safe working of the anti-surge device/system, also relevant technical literature if any in the matter are welcomed. Considering the nature of work it must be noted while quoting the rate, the agency will be totally responsible for the safe design, reliability of the system and each activity, parameter suggested & conducted.

The budgetary offers should be reached to the Division office within the period of 10 days from the date of publishing (03.03.2021)

Sr. No.	Description	Unit.	Qty.
1.	Design, Manufacturing, Supply, Erection, Testing & Commissioning of Non slam type with minimum vibrations Zero Velocity Valve (2400 mm, PN 1.6) for Urmodi Stage II, RM 3, Lift Irrigation Scheme, Tal. Koregaon, Dist. Satara, Maharashtra State as a anti-surge device. The work includes site clearance, cutting of existing 2400 mm dia. pipe, removing the cut portion and erecting the ZVV, etc.	No	1
2.	Design, Manufacturing, Supply, Erection, Testing & Commissioning of Vacuum breaker cum Air Cushion Valves dia 300 mm. on RM 3 at required chainages for Urmodi Stage II LIS, required as part of above anti-surge system.	Nos.	4
3.	Supply, Erection & Testing of 250 mm Butterfly valve (isolation) including cost of transportation, loading, unloading,& erection etc.	Nos.	4

This information is required for the purpose of framing of working estimate and hence the urgency.

Office of the Executive Engineer,
 Mechanical Division,
 MDK/TS-2/554/2020 Date : 17.02.2021
 Tarabai Park, Kolhapur PIN- 416003
 Phone/ fax No. 0231/ 2651284
 e-mail: eemdkop@gmail.com

sd/-
(S. M. Bagewadi)
 Executive Engineer
 Mechanical Division
 Kolhapur