

RATE PROFORMA				
GOVERNMENT OF MAHARASHTRA				
WATER RESOURCES DEPARTMENT				
Bugetory Offer No.7				
Issue Date-16/07/2015 Closing Date - 23/07/2015				
Executive Engineer, Lift Irrigation Mechanical Division No.1, Bhandara				
Sealed Rates are invited by the Executive Engineer, Lift Irrigation Mechanical Division No.1, Bhandara (Phone No.07184 – 252166) for the purpose of estimation of the following works.				
Budgetory offer for Control room Incomer Panel repair work at Tekepar Lift Irrigation Scheme				
Dist.Bhandara				
Qty	Unit	Description of work	Rate Rs. P	Rates to be quoted by
1	Job	Supply,Erection,Testing & Commissioning of existing Incomer Panel No.1 including following work		
1	No	a) Supply,Erection,Testing & Commissioning of IDMTL Relay - (CDG 61 , 5A & 1A)		
1	No	b) Supply,Erection,Testing & Commissioning of Under Voltage Relay (VAGM 22 , 40-80 %)		
1	No	C) Supply,Erection,Testing & Commissioning of High Speed Tripping Relay (VAJH 13)		
1	No	d) Supply,Erection,Testing & Commissioning of Definite Time Relay (VTT 11, 6-60 sec)		
3	Nos.	e) Supply,Erection,Testing & Commissioning of 6.6 KV single phase current Transformer CT ratio <u>800/ 5/5/5A</u> CL 1.0 5P10 PS Burden - 15VA for each core		
3	Nos.	f) Supply,Erection,Testing & Commissioning of 6.6 KV /110 Volt single phase Potential Transformer v3 v3 Burden - 150 VA , CL 1.0		
1	Job	g) Fault finding & repairing of circuit & circuit equipment		
1	Job	h) Testing & Commissioning of provided 6.6 KV , 800 Amp minimum oil circuit breaker		

Executive Engineer
Lift Irrigation Mechanical Division
No.1 Bhandara