

MAHARASHTRA KRISHNA VALLY DEVELOPMENT CORPORATION PUNE 411011 (A GOVT. OF MAHARASHTRA UNDERTAKING) Rates for the supply of measuring instruments for performance testing of pumps & allied equipments as shown below are invited from contractors having experience of the said work for estimate purpose. Please submit the rate to The Executive Engineer, Takari Mechanical & Electrical Division, Warnali, Sangli 416415 Maharashtra within 10 days from date of publishing.			
Name of Work :- Design, Manufacturing, supply, erection, testing & commissioning of submerged centrifugal pumps of 488 HP x 4 Nos. with allied electromechanical equipments etc at Mhaisal 6B. Tal- Jat Dist. - Sangli.			
Item No.	Description	Qty.	Unit
1	Submerged Centrifugal Pump-488HP Design, Manufacturing, Supply, erection, testing & commissioning of submerged centrifugal pumps with motor, non clog type, complete with strainer, suction bell, impeller assembly, discharge case/ Discharge tee, Flexible couplings, base frame Foundation, Guide rail, etc And giving test to full capacity. Suitable for following duties:	4	No
	a) Duty point discharge per pump = 0.35 M3/sec.		
	b) Duty point head = 82.44 Mtr.		
	c) Maximum rpm synchronous = 1500		
	d) No. of stage = 2 stage		
	e) Max. No of pumps working in parallel = 4		
	f) Motor Capacity (including 20% power margin) = 430KW		
	g) Voltage rating = 415 Volts		

This information is required for the purpose of framing of working estimates and hence the urgency. This Budgetary offer is also available on website www.mahayantriki.gov.in

Executive Engineer,
Takari Mech. & Elect.Division,
Sangli