

“डिजीटाईज्ड कालबद्ध सेवा वर्ष -२०१५”

“जलसंपदा विभागाच्या संकेतस्थळास कृपया भेट द्या-<https://wrd.maharashtra.gov.in>”

जा. क्र./ २७३० /यांउसिविक्र.२/चंद्र/तां.शा.२/२०१५	कार्यकारी अभियंता, यांत्रिकी उपसा सिंचन विभाग क्र.२, बल्लारपुर रोड,बाबुपेठ, चंद्रपूर-४४२४०३ यांचे कार्यालय
☎ :- (०७१७२) २२७३८२	
फॅक्स :- (०७१७२) २२७३८२	
ई.मेल :- mlidn2@rediffmail.com	
	दिनांक :- ०६ /१०/२०१५

प्रती,

मा. अधिक्षक अभियंता (यां.),
यांत्रिकी मंडळ,
नागपूर.

विषय :- जिबगाव उपस सिंचन योजना जि.चंद्रपूर.

१) LT motor क्षमता ७५कि.वॅ./१००एच.पी. सदोष असणेबाबत.

२) ३१५ के.व्ही.ए.पॉवर ट्रान्सफॉर्मर सदोष असणेबाबत.

सदर कामाचे अंदाजपत्रक तयार करण्याकरीता budgetary offer मागविणेबाबत.

संदर्भ :- १) उप अभियंता, उपसा सिंचन यांत्रिकी व विद्युत उपविभाग क्र.२, चंद्रपूर यांचे पत्र क्र. २३८/तां.शा/
उसियांवविउविक्र.२ /चंद्र /२०१५ दिनांक २८/०९/२०१५.

२) कार्यकारी अभियंता, चंद्रपूर पाटबंधारे विभाग,चंद्रपूर यांचे पत्र क्र.४२८२/२०१५
दिनांक१४/०९/२०१५.

महोदय,

उपरोक्त विषयाचे अनुषंगाने जिबगाव उपस सिंचन योजना जि.चंद्रपूर.योजनेवरील

१) LT motor क्षमता ७५कि.वॅ./१००एच.पी. सदोष असणेबाबत.

२) ३१५ के.व्ही.ए.पॉवर ट्रान्सफॉर्मर सदोष असणेबाबत.

दरपत्रके मागविण्याकरीता या पत्रासोबत पाठविण्यात येत असलेली बजेटरी ऑफर क्र. ७ (सन २०१५-२०१६) यांत्रिकी

संघटनेच्या संकेत स्थळावर (<https://wrd.maharashtra.gov.in>) प्रसिद्ध करण्याची कार्यवाही करण्याचे करावे ही विनंती.

कार्यालयाचे नाव व पत्ता	कार्यकारी अभियंता, यांत्रिकी उपसा सिंचन विभाग क्र. २, बल्लारशा रोड, बाबुपेठ, पोलिस चौकीजवळ, चंद्रपूर ४४२ ४०३ ई.मेल :- mlidn2@rediffmail.com
बजेटरी ऑफर प्रसिद्ध करण्याची अंतीम तारीख	दिनांक १२/१०/२०१५
बजेटरी ऑफर पाठविण्याचा कालावधी	जाहीरात प्रसिद्ध झाल्यापासून ७ दिवस

सहपत्र :- बजेटरी ऑफर क्र. ७ (सन २०१५-२०१६)

एक प्रतीत

कार्यकारी अभियंता,
यांत्रिकी उपसा सिंचन विभाग क्र.२,
चंद्रपूर

Budgetary Offer No.7

A) Name of Work: Removing, Dismantling, Repairing,Rewinding Assembling, Re-erection and giving test and trial of L.T. Induction Motor at Jibgaon Lift Irrigation Scheme.Tah. Saoli Dist.- Chandrapur.

Sr.No.	Qty	Description of Item	Rate	Unit	Amount
1	1	Item No.1:- Repairing and Rewinding of Foot Mounted Motors SPDP squirrel cage induction motor, conforming to IS 325 having continuous rating suitable for operation at 415 Volts +/- 10%, 3 Phase, 50 Hz +/-3% with "F" class insulation temperature rise limited to class "B" insulation b) minimum kw rating of motor - 75 kw/100HP c) Full load current - 130 AMP d) Efficiency - 89% e) Running speed -1470 rpm f)Wt. of Motor -----Kg. Note.:- All above parameters are subject to tolerance as per IS-325.		Job	
2	1	Item No.2:- Giving satisfactory test and trail of squirrel cage induction motor with Pump against specification mention under item no.1		Job	
(Inclusive of all Taxes)Total Rs					

B) Name of Work: Removing, Dismantling, Repairing,Rewinding Assembling, and giving test and trial of 315 KVA Power Transformer at Jibgaon Lift Irrigation Scheme.Tah. Saoli Dist.- Chandrapur.

Sr.No.	Qty	Description of Item	Rate	Unit	Amount
1		Repairing,Rewinding HV/LV Coils, Revarnishing & Re-Insulating of all Coils,Replacement of damaged HV/LV Brass Rods, Oil glass & other damaged parts & Re-Assembling, and giving test and trial of 315 KVA Power Transformer			
		a)KVA Capacity:--315 KVA.			
		b)Volts ... HV---11000 V, LV---433V..			
		c)Amperes-----HV---16.53 Amps, LV---420 Amp..			
	1Job	d)Phases---- HV---3, LV---3 ..		Job	
		e)Sr. No.----- 2139			
		f)Vector Dig.----Dy 11,..... g) Impedance Volts---5			
		h)Winding----DPC Copper i)Wt. of Core & Winding---687 Kgs.			
		j)Total Wt.-----1612Kgs k)Wt. of Oil---430 Kgs.			
		l)Qty. of Oil---500 Ltrs.			
2	1Job	Item No.2:- Giving satisfactory test and trail of Power Transformer at Site against specification mention under item no.1		Job	

**Dismantling, Transportation is Separately given as per
CSR RATE.**

Executive Engineer
Mech.Lift Irrigation
Division No.2, Chandrapur.

